
Agenda


- Overview of Flex
- ONF QA and Flex PODs
- ☐ CORD Certification Program
- ☐ SEBA POD
- □ SEBA Test Cases
- □ SEBA Test Results
- What's next with Flex & ONF QA




We are Flex – Manufacturing & Design



Compute redistributes due to new workloads demands



Multiple edges, multiple technologies





CORD: Next gen COs for the Service Providers

CORD: Central Office Rearchitected as Data Centers

Economies of a Datacenter

Infrastructure built with a few commodity building blocks using open source software and white boxes

Agility for Service Provider

SDN enabled datacenter platforms enable rapid creation of new services





Access to unique insights





Flex and CORD Relationship



Joined CORD in 2016



Resource and Lab Contribution



Today QA Lab for CORD



Flex journey from CORD 1.0 to CORD 6.0 and beyond

H2 2016

CORD 1.0

FIRST

Creamy-Vegetable

H1 2017

CORD 2.0

SECOND

Mysterious-Decision

H1 2017

CORD 3.0

THIRD

Dangerous-Addition

H₂ 2017

CORD 4.0

FOURTH

Shared-Delusion

H1 2018

CORD 5.0

FIFTH

Satisfying-Cactus

H2 2018

CORD 6.0

SIXTH

Quizzical-Purpose



Key development:

- CORD-in-a-box deployments
- Single node cluster



Key development:

- Manual CORD deployments in lab
- Multi-node POD with 10G fabric network



Key development:

- Automated CORD deployments using Jenkins
- Multi-node POD with 40G fabric network



Key development:

- CORD community lab with remote connection facility
- Onboard partner test tools



Key development:

- Published CORD5.0 QA reports
- OCP based multinode community POD



Key development:

- Contribution to CORD Certification Program
- SEBA test plan demonstration





POD Level Deployments at Flex






Flex "CloudLabs" VPN Network









ONOS: Dev/Test

CORD: Full Fabric


CORD: Full Fabric on OCP

SEBA: Test Plan





SEBA is first certification domain





Source: https://wiki.opencord.org/display/CORD/Certification+Brigade

Reference Designs

SEBA Certification flow

Vendor interested in certification

Contact Certification Brigade Participant form submission

Selection of ACL

Test service logistics: schedule, fee, test process

Testing in ACL

Results review


Logo granted by SC








QA Labs and CORD Certification Program







SEBA POD Architecture

Hardware


- 1 physical AGG switch (Tomahawk)
- 3 compute nodes connected to AGG switch
- Up to 16 EdgeCore OLTs with NNI port connected to the AGG switch
- Up to 64 ONUs on each PON port
- 1 GE management switch to which all OLTs AGG and compute node management ports

Virtualization

- Gateway VM instantiated on one of the compute nodes
- Abstract OLT instantiated on one of the compute nodes

External


BNG, DHCP Server(RG & POD),
 Radius Server, External OSS, Public
 Internet







SEBA POD Architecture at Flex



Accton AS6712-54X Leaf and Spine Switches 48x 40G, 6x 40G

Flex Platform

- 2x Intel E5-2630v3 8c 2.4Ghz, 192GB RAM
- 2x1G, 2x40G dual port Mellanox NIC
- 1x Intel SSD 480GB

1G IPMI/Mgmt/External Network 40G Fabric Network Subscriber Traffic Network


Internet



External switch




ONF Jenkins Nightly-Builds for Flex SEBA POD






SEBA POD UI: CORD 6.0






Validate: SEBA POD 'Fastpath' Network Traffic Flow





'Fastpath' Network Flow Validation on SEBA POD



RG@ubuntu:~\$ nohup ping 10.8.2.100 > ping_log.txt &

RG -> OLT -> Fabric -> Destination

Onos ui: http://10.192.4.241:30120/onos/ui/index.html#/topo onos/rocks



Automated SEBA Test Plan

SN	Group	Test	TestCase ID	Results Pass/Fail
test1	Verify End-end ping with ONU in Correct Location	Configure whitelist with correct ONU location Validate successful authentication/DHCP/E2E ping	ATT_Test001	
test2	Test by removing ONU from Whitelist, and re-add ONU to Whitelist for a successful ping	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with correct ONU location Validate successful authentication/DHCP/E2E ping Remove ONU from whitelist Validate failed authentication/DHCP/E2E ping Add ONU to whitelist Validate successful authentication/DHCP/E2E ping	ATT_Test001	FAIL
test3	Test with ONU in Wrong Location and re-add ONU in Correct Location for a successful ping	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with correct ONU location Validate successful authentication/DHCP/E2E ping Update whitelist with wrong ONU location Validate failed authentication/DHCP/E2E ping Update whitelist with correct ONU location Validate successful authentication/DHCP/E2E ping	ATT_Test001	FAIL
test4	Test by Removing Subscriber and re-creating the Subscriber for a successful ping	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with correct ONU location Validate successful authentication/DHCP/E2E ping Remove subscriber model Validate successful authentication (expected with the ONF pod setup) but failed DHCP/E2E ping Recreate subscriber model Validate successful authentication/DHCP/E2E ping	ATT_Test001	PASS
test5	Test by Skipping Subscriber Provisioning and re-provisioning Subscriber	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with correct ONU location and skip provisioning subscriber Validate successful authentication (expected with the ONF pod setup) but failed DHCP/E2E ping Provision subscriber Validate successful authentication/DHCP/E2E ping	ATT_Test001	PASS




Automated SEBA Test Plan

SN	Group	Test	TestCase ID	Results Pass/Fail
test6	Test by skipping Authentication	Validates failed authentication/DHCP/E2E Ping with the following scenario: Configure whitelist with correct ONU location and skip RG authentication Validate failed authentication/DHCP/E2E Ping	ATT_Test001	PASS
test7	Test with ONU not in Whitelist	Validates failed E2E Ping Connectivity and object states for the given scenario: Skip whitelist configuration for ONU Validate failed authentication/DHCP/E2E ping	ATT_Test001	PASS
test8	Test with ONU not in Whitelist and by skipping Subscriber Provisioning	Validates E2E Ping Connectivity and object states for the given scenario: Skip whitelist configuration for ONU and subscriber provisioning Validate successful authentication but failed DHCP/E2E ping Configure whitelist with correct ONU location Validate successful authentication (expected with the ONF pod setup) but failed DHCP/E2E ping Provision subscriber Validate successful authentication/DHCP/E2E ping	ATT_Test001	PASS
test9	Test with ONU in Wrong Location	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with wrong ONU location Validate failed authentication/DHCP/E2E ping	ATT_Test001	PASS
test10	Test with ONU in Wrong Location and Skip Subscriber Provisioning, Then fix ONU in Correct Location and Provision Subscriber	Validates E2E Ping Connectivity and object states for the given scenario: Configure whitelist with wrong ONU location and skip subscriber provisioning Validate failed authentication/DHCP/E2E ping Configure whitelist with correct ONU location Validate successful authentication (expected with the ONF pod setup) but failed DHCP/E2E ping Provision subscriber Validate successful authentication/DHCP/E2E pingl	ATT_Test001	PASS



ONF Jenkins Test Automation for Flex SEBA POD





Stage View

ld History	trend -							
	х			Parse deployment	Download Cord Tootor	Test	Subscriber Validation	Publish tes
Nov 29, 2018 12:33 PM				configuration	Reno	Configurations	and Ping Tests	results
Nov 28, 2018 10:55 PM				IIIC				
Nov 28, 2018 9:19 PM		Average stage times:		2 s	10s	525ms	1h 1min	19s
Nov 28, 2018 8:59 PM					-			
Nov 28, 2018 12:33 PM		#110						
Nov 27, 2018 11:31 PM	34,	Nov 29 1 04:33 commit		2s	10s	525ms	1h 1min	19s
Nov 26, 2018 12:31 PM								
Nov 25, 2018 12:32 PM								



Configure

Rename

find

#110

#109

Full Stage View

Pipeline Syntax

Build History

Mary Job Config History

Flex SEBA POD: Test Summary

ATT Test001 Test Report

Generated 20181128 14:07:42 GMT-08:00 1 day 2 hours ago

Summary Information

Status: 2 critical tests failed

Documentation: Test various end-to-end scenarios with ATT workflow

 Start Time:
 20181128 13:19:07.911

 End Time:
 20181128 14:07:29.210

Elapsed Time: 00:48:21.299

Log File: log-ATT_Test001-20181128-140729.html

Test Statistics

Total Statistics	\$	Total \$	Pass \$	Fail \$	Elapsed \$	Pass / Fail
Critical Tests		10	8	2	00:48:20	
All Tests		10	8	2	00:48:20	
			_			
Statistics by Tag	\$	Total \$	Pass \$	Fail \$	Elapsed \$	Pass / Fail
test1		1	1	0	00:03:04	
test10		1	1	0	00:05:46	
test2		1	0	1	00:08:52	
test3		1	0	1	00:01:54	
test4		1	1	0	00:05:22	
test5		1	1	0	00:04:35	
test6		1	1	0	00:04:00	
test7		1	1	0	00:04:09	
test8		1	1	0	00:06:26	
test9		1	1	0	00:04:13	
Statistics by Suite	\$	Total \$	Pass 💠	Fail \$	Elapsed \$	Pass / Fail
ATT Test001		10	8	2	00:48:21	



Flex SEBA POD: Test Execution Log

Test Execution Log

- SUITE ATT Test001 Full Name: ATT Test001 Documentation: Test various end-to-end scenarios with ATT workflow Source: /var/jenkins/workspace/build_att-workflow_flex-pod1-olt_master_test/cord-tester/src/test/cord-api/Tests/WorkflowValidations/ATT_Test001.robot Start / End / Elapsed: 20181128 13:19:07.911 / 20181128 14:07:29.210 / 00:48:21.299 Status: 10 critical test, 8 passed, 2 failed 10 test total, 8 passed, 2 failed + SETUP Setup Suite + TEARDOWN Teardown Suite **★** TEST ONU in Correct Location TEST ONU in Correct Location -> Remove ONU from Whitelist -> Add ONU to Whitelist **★ TEST ONU in Correct Location -> ONU in Wrong Location -> ONU in Correct Location** + TEST ONU in Correct Location -> Remove Subscriber -> Create Subscriber **★** TEST ONU in Correct Location (Skip Subscriber Provisioning) -> Provision Subscriber ◆ TEST ONU in Correct Location (Skip Authentication) TEST ONU not in Whitelist ■ TEST ONU not in Whitelist (Skip Subscriber Provisioning) -> Add ONU to Whitelist -> Provision Subscriber + TEST ONU in Wrong Location **★** TEST ONU in Wrong Location (Skip Subscriber Provisioning) -> ONU in Correct Location -> Provision Subscriber



Demo

- Subscriber node: cluser@10.192.4.61

 nohup ping 10.8.2.100 > ping log.txt &
- DHCP node: cord@10.192.4.62

 sudo tcpdump -eni ens3>tcpdump.txt (service tags)
- ONOS UI: http://10.192.4.241:30120/onos/ui/index.html#/topo onos/rocks
- CORD UI: http://10.192.4.241:30001/#/dashboard
- Jenkins: https://jenkins.opencord.org/view/ATT-Workflow/job/build_att-workflow_flex-pod1-olt_master/
- Test Results:


https://jenkins.opencord.org/view/ATT-Workflow/job/build_att-workflow_flex-pod1-olt_master_test/




Summary and Next Steps

Customer, Partner and Community Engagement Lab

- Continue working on comprehensive plan to test, validate and certify CORD platform and components using Flex SEBA POD
- Continue collaborating with ONF Certification Brigade to define CORD Certification program (CCP) and its execution
- Extend in house automated test and validation framework to validate CORD platform and components with Flex SEBA POD
- Collaborate with Vendors & Service Providers to demonstrate Telco usecases and support CORD deployments









Thank You!

For collaboration and questions please send email to Siddharth.Gogar@flex.com